

electrics :: plumbing :: heating


t: 01271-828077

e: info@theworksmb.com

w: www.theworksmb.com

## 4 - Bed New Build

Spring 2012



**Existing Insulation:** Current building regulation.

<u>Additional Options:</u> FTC3 controls with built in weather compensation and 2kw electric back up (hydrobox).

Back Up: Wood burner.

Heating System: Full underfloor heating, 300l unvented hot water.

<u>Airsource Unit:</u> 14kw ECODAN unit producing 100% of heating and hot water.

## **Customer comment:**

"We have chosen this system over a conventional oil boiler as there is no mains gas in the village and for its low running cost.

The system is easy to use you just set it and forget about it, which is great."

